

QUOTATION SC628/2009

PAVING OF PROTEA ROAD – BETTY’S BAY

1. Extent of works:

Quotations are herewith invited for the paving of an existing gravel road approx. 80m long (4m wide) in Betty’s Bay. The base will be prepared and shaped by others. The road will have a crossfall with a CK5 kerb on the lower side and a brick header course in concrete on the other side. All materials must comply with SANS 1200 MK and SANS 1200 MJ

See attached plan and photograph of the existing road.

2. Quantities:

Item	Quantity	Rate	Total
1. Supply and lay Class 25 concrete interlock paving 80mm thick, inclusive off sand bedding, grouting and all cutting works (colour – grey)	320m ²		R
2. Supply Class 25 concrete interlock paving 80mm thick only (colour –grey)	320m ²		Rate only
3. Supply, lay, joint, grout and backfill in concrete, type CK5 kerb	80m		
4. Supply type CK5 kerb only	80m		Rate only
5. Brick header course in concrete	80m		
<u>Total</u>			R

3. Conditions:

1. The contractor must provide all materials, plant and labour (unskilled labour **must** be sourced locally) to complete the works.
2. The works must be completed within a period of 4 weeks from date of acceptance of the quotation (penalty of R300/day for late completion).
3. The contractor must remove and dispose of any spoil materials and leave the works neat and tidy on completion.
4. Quoted rates must **exclude VAT**

I of hereby
(Name) (Company)

quote the amount of R (vat excluded) for the
completion of the works as described and specified above.

.....
(signature)

.....
(date)