



OVERSTRAND MUNICIPALITY

TENDER NO. SC 934/2010

DAVIES POOL HAND RAIL

Name of Tenderer : _____

Address : _____

Contact person : _____

Tel. no. : _____

Fax no. : _____

(Pricing schedule on page 2)

Issued by: Dion van Vuuren

**Overstrand Municipality
Directorate: Community Services
P.O. Box 20
HERMANUS
7200**

Tel. no. : 028 3138112

Fax no. : 028 3131111

DAVIES POOL HAND RAIL

SPECIFICATIONS:

Quotations are hereby invited for the supply and installation of a 40 m long and 1,2m high hand rail, at Davies Pool below the Onrus Caravan Park.

Materials & Construction

Steel Alloy boiler tubing of a 60mm (2.5 inch) diameter and with a wall thickness of 3mm is to be used. The top of the pillars are to be cut to cradle the hand rail. All components are to be brazed together (not welded) using a suitable filler of brass or bronze with a borax or similar flux. This is to limit the formation of oxide. Concrete with a strength factor of at least 30Mpa with an accelerator to ensure rapid curing must be used for the foundations. The minimum sizes of the foundations are to be 500mm x 300mm x 300mm and drilling of two 10 mm diameter tensile steel dowels per foundation into existing rock.

Contract Completion and Guarantee

Construction to be completed within 1 month after awarding of the contract. A compulsory site meeting will be held on the 31 August 2010 at 09H30. Prospective tenderers are required to familiarize them with the site and construction conditions as no claims for any additional work will be entertained. The successful contractor will be expected to guarantee the construction of the hand rail for one year after the successful completion of the project.

Pricing schedule

TENDER AMOUNT:
A: SUPPLY & CONSTRUCTION OF HAND RAIL
AT DAVIES POOL

--

(All prices shall be quoted in South African currency and be inclusive of VAT.)

Signature of tenderer

HAND RAIL SKETCH

